

6-73. During the MIL-STD-462 CE test on power leads, all leads including the neutral which are grounded externally to the equipment must be evaluated.

- a) True
- b) False
- c) Does not apply
- d) None of the above

**Mike Howard, 76**

*Answer: a)*

*E&T Time: 5 Minutes*

*Ref. MIL-STD-462, CE01, p. 13, para 2,  
Applicability CE03, pp. 21-22, para. 2 Applicability.*